



THE CHALLENGE

To remove and replace the existing timber-framed and asbestos-lined extensions with new units as well as installing new foundations on a site that posed the following challenges:

- As the extension being removed contained the only bathroom for the house the replacement had to be completed within a single day to avoid having to relocate the residents.
- Incoming and outgoing services needed to be disconnected from the old units and connected to the new units within the same day.

THE SOLUTION

The existing timber extensions, including any asbestos, were removed using a crane and sent for recycling.

The new, fully fitted out, brick-clad units were manufactured off-site and then delivered by truck. We installed these using a crane and connected them up to the services within the house on the same day to ensure minimal

disruption to residents.

Using our QuadraPile helical pile foundations removed the need to dig and pour concrete, which meant that spoil removal was unnecessary.

Each unit consists of a bathroom, or shower room, and utility room. We have installed over 700 units on this estate, usually completing three in a day.

✓ Minimal disruption

✓ Clean, fast, efficient

✓ No mess foundations

✓ Limited access sites

QUADRABUILD

THE PROCESS



To find out more and to see how we could help you, please contact us

sales@QuadraBuild.com | 02086 445 434 | www.QuadraBuild.com

